



SECTION

NOTES:

- 1 - THE DISTRICT RECOMMENDS CONTRACTOR MEET ALL OF THE REQUIREMENTS ESTABLISHED FOR SAFE TRENCHING (SEE OSHA AND UOSH REQUIREMENTS, LATEST EDITIONS).
- 2 - CONTRACTOR SHALL LOCATE ALL UNDERGROUND UTILITIES BEFORE LAYING PIPE WITHIN 50 FEET OF SAID UTILITIES, WHICH MAY BE EXPOSED, DAMAGED, OR CROSSED AS SHOWN ON THE DRAWINGS OR AS "BLUE STAKED". THE CONTRACTOR WILL MAKE ARRANGEMENTS WITH THE UTILITY COMPANY TO MOVE THE UTILITY IF NECESSARY OR OBTAIN PERMISSION FROM THE DISTRICT ENGINEER TO MODIFY GRADE OF PIPELINE IN ORDER TO GO AROUND UTILITIES.
- 3 - ALL SEWER MAINS SHALL BE BEDDED WITH A MINIMUM OF 12 INCHES OF IMPORTED 1-INCH GRADED GRAVEL UNDER THE PIPE AND 12 INCHES OVER THE PIPE. UNSTABLE CLAYS, ORGANIC SOILS, OR OTHER UNSTABLE BASE MATERIAL MAY REQUIRE A GREATER DEPTH OF BEDDING OR ALTERNATE MATERIALS.
- 4 - TRENCH FILTER FABRIC SHALL BE FURNISHED AND INSTALLED BETWEEN THE BEDDING AND BACKFILL MATERIAL FOR ALL SEWER MAINS.

SCALE: NONE

ORIGINAL	
04/17/2019	LBH
REVISIONS	
07/14/2020	LBH

SOUTH DAVIS SEWER DISTRICT STANDARD SEWER MAIN TRENCH DETAIL



SHEET:

114-1