

## NOTES:

- 1 THE UPPER END OF EACH CLEANOUT SHALL HAVE A SCREWED BRASS OR IRON CAP AND SHALL TERMINATE AT FINISH GRADE AFTER FINAL LANDSCAPING. IN PAVED AREAS, A TRAFFIC-RATED BOX AND CAST IRON LID MUST BE SET OVER THE SCREWED BRASS OR IRON CAP (SEE DETAIL SHEET 104-2).
- 2 ADDITION OF A DOUBLE-SWEEP CLEANOUT ON AN EXISTING VITRIFIED CLAY OR CONCRETE LATERAL REQUIRES USE OF SHEAR BAND COUPLER FITTINGS. THE FITTINGS SHALL BE SHADED IN SALT FROM THE SPRINGLINE UP TO THE TOP OF THE FITTING.

SCALE: NONE

ORIGINAL			COUTH DAVIC CEMED DISTRICT
04/01/2019	LBH	,	SOUTH DAVIS SEWER DISTRICT
REVISIONS			
05/25/2023	LBH		DOUBLE-SWEEP CLEANOUT DETAIL



SHEET: 123-3